

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.**JANAPATH, BHOINAGAR, BHUBANESWAR - 22****[Electrical Division]****Ph: 0674-2541545, 2542921, Fax: 0674-2541543****E-mail :- pmelectricalophwc2025@gmail.com, Website: www.ophwc.com /www.ophwc.nic.in****PRICE BID FOR THE WORK UNDER SL. NO :- 29 AS PER IFB****NAME OF THE WORK :- SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF LIGHTNING PROTECTION SYSTEM AT SPECIAL SUB-JAIL, DEOGARH IN THE DISTRICT OF DEOGARH.****BID REF NO :- 65/PM/ELECT/OPHWC/2024-25****NAME &
ADDRESS
OF THE
FIRM****SCHEDULE OF WORKS**

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
1	40002086 AAir-Terminal Supply, Installation, Testing & Commissioning of Early Streamer Emission (ESE-30))type Lightning Air Terminal. Supporting Mast The mounting pole used to support the lightning air terminal shall be minimum length of 05 Mtr. , non corrosive and made up of medium class GI / SS pipe of 1.5" diameter having base plate at bottom for securely fixing the mast on roof top. The mounting pole and supports shall be securely fixed with the brackets and PVC insulated metallic guy wires to withstand the maximum wind velocity of that area. Protection Radius :- 48 Mtr Make :- ABB / STROMKING All the work should be carried out as per the specified specifications and instruction of the Engineer-in-Charge.	NO	2	99250	198500.00
2	40002095 Supply, Installation, Testing & Commissioning of maintenance free chemical earthing having enhancing chemical compound with 3 Mtr. Long copper bonded steel rod and suitable termination clamp including all accessories. Make :- ABB / STAR-X / UNIVERSAL All the work should be carried out as per the specified specifications and instruction of the Engineer-in-Charge.	NO	4	16650	66600.00

3	40002720 Supply and laying of 70sqmm single core FR PVC insulated unseathed copper conductor for voltage grade 1100 volt as per IS-694 in sur face/underground as required(sl no-5.5.2)(Make-KEI/FINOLEX/HAVELLS)	MTR	55	1068.92	58790.60
	Total Rs.				3,23,890.60
	Cess @ 1%				3,238.91
	Total Estimated Cost				3,27,129.51
	Total Estimated Cost in Figures				3,27,130.00
EXCESS	<input type="checkbox"/> LESS <input type="checkbox"/> (Please Tick)	_____ %			
Quoted Amount in Figure					
Quoted Amount in word					

N:B- The Estimated cost is exclusive of GST .

Signature of Tenderer with seal

Sd/-
Asst. Project Manager (Elect)

Sd/-
D.M (Elect)

Sd/-
Project Manager (Elect)