THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD. JANAPATH, BHOINAGAR, BHUBANESWAR - 22

[Electrical Division]

Ph: 0674-2541545, 2542921, Fax: 0674-2541543

E-mail:- pmelectricalophwc2025@gmail.com, Website: www.ophwc.com

PRICE BID FOR THE WORK UNDER SL. NO :- 03 AS PER IFB

NAME OF THE WORK :- EXTERNAL ELECTRIFICATION WORK FOR POWER SUPPLY TO 6-E+6-F TYPE STAFF QUARTERS AT MUNIGUDA POLICE STATION IN THE DISTRICT OF RAYAGADA.

BID REF NO.- 69/PM/ELECT/OPHWC/2025-26 NAME & ADDRESS OF THE FIRM

SCHEDULE OF WORKS

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.				
				RATE IN RS.	AMOUNT IN RS.			
PART-I	Refrbishment of 100 KVA 11/0.4KV sub station - 1 No.							
1	11KV AB switch 3 pole(400 Amp, 50 Hz, Horizontal type)	Set	2	16827.00	33654.00			
2	11KV HG fuse 3 pole(400 Amp, 3 pole, 50 Hz)with PI	Set	2	16372.00	32744.00			
3	11 KV LA(9 KV, 10 KA)Station class	No.	6	1420.00	8520.00			
4	GI Pipe earthing 40 Dia Medium gauge 3 mtrs long for earthing device	No	14	1491.00	20874.00			
5	25x6 mm GI flat for earthing	Kg	140	106.50	14910.00			
6	LT Distribution box with MCCB, Aluminium Bus bar for 2 bay with Kitkat Fuse for 100 KVA S/S	No	2	34674.98	69349.97			
7	GI Nuts, Bolts and washers of assorted size	Kg	25	110.76	2769.00			
8	55 sq. mm AAAC	Km	0.1	42600.00	4260.00			
9	150 sq. mm 1 core LT XLPE Cable(armoured)(From Transformer LT Bushing to LTDB I/C and LTDB O/G to Zero Pole)	Mtr.	80	298.20	23856.00			
10	Earthing Device coil type GI	No	4	235.72	942.88			
11	No.6 GI wire	Kg	1.048	106.50	111.61			
12	Sundries(Pole Numbering, Zebra painting, Binding wire and other acessories)	Ls	1	2000.00	2000.00			
	Total Rs.							

PART-III	LT LINE-0.110 Km(4x50+1x50+1x16) sq. mm AB Cable						
13	8 Mtr. Long 200 KG PSC Pole	No	3	2840.00	8520.00		
14	4x50+1x50+1x16 sqmm AB Cable	Mtr.	115.50	206.22	23818.41		
15	Pole clamp for eye Hook for AB cable	No	4	284.00	1136.00		
16	Dead end clamp suitable for XLPE cable	No	2	92.30	184.59		
17	Eye hook for AB Dead End cable	No.	2	85.20	170.41		
18	Suspension clamp with I Hook for ABC	No.	2	482.80	965.60		
19	L.T Stay set (Complete)	Set	3	738.40	2215.20		
20	L.T Stay Insulator	No.	3	42.60	127.80		
21	L.T Stay Clamp(1.4 K.g/Pair)	Pair	3	156.20	468.60		
22	7/12 SWG Stay Wire	Kg	24	106.50	2556.00		
23	Base plate for support	No.	3	408.00	1224.00		
24	GI Nuts and Bolts of assorted size	Kg	2	110.76	221.52		
25	Earthing device coil type(GI)	No	3	235.72	707.16		
26	No. 6 GI wire for earthing	Kg	0.786	106.50	83.71		
27	Insulated piercing connector. Type-A-main 16 to 95 sq.mm to Tap-16 to 95 to 10 sq.mm	No	7	113.60	795.21		
28	Insulated piercing connector. Type-B-main 16 to 95 sq.mm to Tap-2.5 to 10 sq.mm	No	7	56.80	397.58		
29	Danger Board	No.	3	113.60	340.80		
30	GI clamp for Danger Board GI Flat (25x3 @ 0.6 Kg/Mtr.)510 mm Length(0.306 Kg/piece)	Kg	0.9027	106.50	96.14		
31	Sundries(Zebra painting, Piercing connector, Insulation Tape and other acessories)	Ls	1	1000.00	1000.00		
	Total R	45,028.72					
	A.Sub Total Rs.						
В	Stock, storage and insurance (@3% on A)	7770.61					
С	TOTAL RS.				266790.79		
D	T&P @ 2% of C	5335.82					

Е	Contigency @ 3% of C	8003.72				
F	Transportation @ 7.5% of C	20009.31				
G	Erection charges @ 10% on others ,5% on Disand 20% on PSC poles	27556.64				
Н	TOTAL RS.	327696.28				
32	Cement concrete for Stud/Stay Anchor Plate with (1:2:4),0.2 cum @6177.92	Nos.	3	1329.77	3989.31	
33	Couping of poles in ratio 1:1:5:3, 0.1125 cum @6400	Nos.	3	748.00	2244.00	
34	Concreting of PSC poles in ratio 1:1:5:3=0.375 cum @6400	Nos.	3	2493.98	7481.94	
35	Materials for earthing including massonary work for eathpit & cement plate cover with salt, charcoal etc.	No	14	1600.00	22400.00	
36	Brick Boundary wall with Gate(For 2 Nos. 100 KVA S/S)	Mtr.	24	7300.12	175202.8475	
					211318.10	
				Sub Total Rs.	539,014.38	
	Cess @ 1%					
		544,404.52				
		544,405.00				
EXCESS	LESS (Please Tick)				%	
	Quoted Amount in Figure					
	Quoted Amount in word					

N:B- The Estimated cost is exclusive of GST.

Signature of Tenderer with seal

Sd/-Asst. Project Manager (Elect) Sd/Dy. Manager (Elect)

Sd/-Project Manager (Elect)