

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.**JANAPATH, BHOINAGAR, BHUBANESWAR - 22****[Electrical Division]****Ph: 0674-2541545, 2542921, Fax: 0674-2541543****E-mail :- pmelectricalophwc2025@gmail.com, Website: www.ophwc.com /www.ophwc.nic.in****PRICE BID FOR THE WORK UNDER SL. NO :- 01 AS PER IFB****NAME OF THE WORK :- SITC OF 1 NO OF AIR CONDITIONER AT SUB DIVISION OFFICE , ROURKELA AND 1 NO OF AIR CONDITIONER AT SUB DIVISION OFFICE , ANGUL UNDER SAMBALPUR DIVISION.****BID REF NO :- 63/PM/ELECT/OPHWC/2024-25****NAME &
ADDRESS
OF THE
FIRM****SCHEDULE OF WORKS**

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
1	40000988 Point wiring for 15/16 amp socket outlet (MODULAR) with 4.0sq.mm FR PVC insulated single core multistrand copper conductor ISI marked in recess 20 mm dia non metallic PVC flexible conduit with 15/16 Amp, 250 V modular type switch & socket , phenolic laminated sheet suitable size ISI marked MS Box & earthing Point with 1 x 1.5 sq.mm FR PVC insulated single core multistrand copper conductor for loop earthing etc . (Make of wire Finolex / Anchor / Havells/ V guard/KEI) Make-switch/Socket-Legrand /Wipro-North West /Anchor-Panasonic/ havells). (Make of PVC pipe-AKG/NORPACK)	NO	1	1034.83	1034.83
2	40001003 Recessed wiring to submain in 2 x 4 sqmm FR PVC insulated single core multistarnd copper conductor of ISI marked confirming to IS-694/1990 in 20 mm dia non metallic heavy duty flexible conduit 1.6 mm thick along with 1 x 1.5 sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required (Make of wire Finolex / Anchor / Havells/ V guard/KEI) CSR SL .No- 1.8.3)(Make of PVC pipe-AKG/NORPACK)	MTR	20	186.48	3729.60
3	40001190 Supplying and fixing of Call Bell/buzzer ISI marked suitable for DC/AC single phase 230 volts complete as required (CSR sl no-1.30)	NO	1	135.39	135.39
4	40001833 Supply and fixing of 6 sqmm service wire along with G.I wire for support of service wire including all accessories and connections.(Make-Joshi/Multicab)	MTR	50	46.53	2326.50

5	40008397 Supply and fixing of 4 FT 20 W LED Tube light fitting with lamp including fixing and connections (Make-CROMPTON(MODEL NO-CCS-102- 20-65-SL-DP-NWH/ PHILIPS(MODEL NO-SLIMLINE NEXT 4'/ WIPRO(MODEL NO-LL20-221-XXX-65NE3)	NO	2	724.13	1448.26
6	40009312 Supply and installation of 1.5Tr.(5 Star) Inverter Split type Air Conditioner with supply and fixing of 4 KVA ,130-280 Volt voltage range wall/floor mounted stabiliser including all accessories,fastner angle copper piping up to 15ft & connections MAKE of A.C. – CARRIER MODEL NO-EMPERIA DXI/BLUE STAR MODEL NO-IA518ENU,MAKE OF STABILIZER-AUTOTEK/V-GUARD/MICROTEK	NO	1	46764.44	46764.44
7	40000949 Recessed wiring to Tube Light Point (MODULAR) with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non metallic PVC flexible conduit with 5 Amp, 250 V one way modular switch ISI marked and ceiling rose ISI marked mounted on MS Box having front bakelight cover of suitable size, MS Box with 1.0 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection. (Make of wire Finolex / Anchor / Havels/ V guard/KEI)(Make-switch/ceiling rose-Legrand /Wipro-North West /Anchor-Panasonic/ havells)(Make of PVC pipe-AKG/NORPACK)	NO	2	1173.86	2347.72
8	40000952 Recessed wiring to Calling Bell Point (MODULAR) with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non metallic PVC flexible conduit with 5 Amp, 250 V modular bell push ISI marked and ceiling rose ISI marked mounted on MS Box having front bakelight cover of suitable size, MS Box with 1.0 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection. (Make of wire Finolex / Anchor / Havels/ V guard/KEI)(Make-bell push switch-Legrand /Wipro-North West /Anchor-Panasonic/ havells)(Make of PVC pipe-AKG/ NORPACK)	NO	1	1315.7	1315.70
SUB DIVISION OFFICE AT ROURKELA					

1	40000988 Point wiring for 15/16 amp socket outlet (MODULAR) with 4.0sq.mm FR PVC insulated single core multistrand copper conductor ISI marked in recess 20 mm dia non metallic PVC flexible conduit with 15/16 Amp, 250 V modular type switch & socket , phenolic laminated sheet suitable size ISI marked MS Box & earthing Point with 1 x 1.5 sq.mm FR PVC insulated single core multistrand copper conductor for loop earthing etc . (Make of wire Finolex / Anchor / Havells/ V guard/KEI) Make-switch/Socket-Legrand /Wipro-North West /Anchor-Panasonic/ havells). (Make of PVC pipe-AKG/NORPACK)	NO	1	1034.83	1034.83
2	40001003 Recessed wiring to submain in 2 x 4 sqmm FR PVC insulated single core multistarnd copper conductor of ISI marked confirming to IS-694/1990 in 20 mm dia non metallic heavy duty flexible conduit 1.6 mm thick along with 1 x 1.5 sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required (Make of wire Finolex / Anchor / Havells/ V guard/KEI) CSR SL .No- 1.8.3)(Make of PVC pipe-AKG/NORPACK)	MTR	20	186.48	3729.60
3	40009312 Supply and installation of 1.5Tr.(5 Star) Inverter Split type Air Conditioner with supply and fixing of 4 KVA ,130-280 Volt voltage range wall/floor mounted stabiliser including all accessories,fastner angle copper piping up to 15ft & connections MAKE of A.C. – CARRIER MODEL NO-EMPERIA DXI/BLUE STAR MODEL NO-IA518ENU,MAKE OF STABILIZER-AUTOTEK/V-GUARD/ MICROTEK	NO	1	46764.44	46764.44
	Total Rs.				1,10,631.31
	Total Estimated Cost				1,10,631.31
	Total Estimated Cost in Figures				1,10,631.00
EXCESS	<input type="checkbox"/> LESS <input type="checkbox"/> (Please Tick)	_____ %			
Quoted Amount in Figure					
Quoted Amount in word					

N:B- The Estimated cost is exclusive of GST .

Signature of Tenderer with seal

Sd/-
Asst. Project Manager (Elect)

Sd/-
D.M (Elect)

Sd/-
Project Manager(Elect)