THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD. JANAPATH, BHOINAGAR, BHUBANESWAR - 22

[Electrical Division]

Ph: 0674-2541545, 2542921, Fax: 0674-2541543

E-mail:- pmelectricalophwc2021@gmail.com, Website: www.ophwc.com/www.ophwc.nic.in

PRICE BID FOR THE WORK UNDER SL. NO:- 06 AS PER IFB

NAME OF THE WORK :- EXTERNAL ELECTRIFICATION WORK FOR POWER SUPPLY TO 6-F TYPE QTRS. AT BISRA FIRE STATION IN THE DIST. OF SUNDERGARH.

BID REF NO: -43/DGM/ELECT/OPHWC/2024-25

NAME &
ADDRESS
OF THE
FIRM

SCHEDULE OF WORKS

SI. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
1	9 Mtr. Long 300 kG PSC Pole	No	9	4080.00	36720.00
2	LT Line with 50 sq. mm AB cable	Km	0.2	252338.48	50467.70
3	LT stay set complete	No	3	707.20	2121.60
4	7/12 SWG Stay wire	Kg	18	102.00	1836.00
5	LT stay clamp	Pair	3	149.60	448.80
6	LT stay insulator	No	3	40.80	122.40
7	11/0.4 KV 63 KVA Transformer,BIS Energy Level-II,Star-I	No	1	117640.00	117640.00
8	Accessories for 11/0.4 KV DP mounted 63 KVA S/S with double disc arrengement alongwith LT Distribution Box with MCCB,Busbar, Kitkat Fuse.	No	1	156529.00	156529.00
Α	TOTAL MATERIAL COST IN RS				365885.50
В	Stock,storage and insurance (@3% on A)				10976.56
С	TOTAL RS.				376862.06
D	T&P @ 2% of C				7537.24
E	Contigency @ 3% of C				11305.86
F	Transportation @ 7.5% of C				28264.65
G	Erection charges of Transformer @ 5% of trnsformer and joist pole				6058.46
Н	Erection charges of PSc Pole@ 20%				7564.32
1	Erection charges for other materials@ 10%				21787.13
	Total Rs.Part-A			40-0	459379.73
9	Concrete material for stay anchor plate	No	2	1652.54	3305.08

10	Padding and concreting material for support	No	9	2837.97	25541.73
	Total Rs.				488226.54
	Cess @1%				4882.27
	Total Estimated Cost				493108.80
	Total Estimated Cost in Figures				493,109.00
EXCESS	LESS (Please Tick)			%	
	Quoted Amount in Figure				
	Quoted Amount in word			_	

N:B- The Estimated cost is exclusive of GST.

Signature of Tenderer with seal

Sd/-Asst. Project Manager (Elect) Sd/-D.M (Elect) I/C

Sd/-DGM Engg.(Elect.)