

**THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.**  
**JANAPATH, BHOINAGAR, BHUBANESWAR - 22**  
**[Electrical Division]**  
**Ph: 0674-2541545, 2542921, Fax: 0674-2541543**  
**E-mail :- pmelectricalophwc2021@gmail.com, Website: www.ophwc.com /www.ophwc.nic.in**

**PRICE BID FOR THE WORK UNDER SL. NO :- 08 AS PER IFB**

**NAME OF THE WORK :- EXECUTION OF EXTERNAL ELECTRIFICATION WORK FOR POWER SUPPLY TO 6-F TYPE QTRS. AT JHARABANDH FIRE STATION IN THE DIST. OF BARGARH.**

**BID REF NO :- 43/DGM/ELECT/OPHWC/2024-25**

<b>NAME &amp; ADDRESS OF THE FIRM</b>	
---------------------------------------	--

**SCHEDULE OF WORKS**

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
1	9 Mtr. Long 150X150 mm RS Joist Pole(30.6 Kg/Mtr.)	No	8	24345.36	194762.88
2	11/.04 KV 63 KVA Transformer (Star-1,BIS/EEL-2)	No	1	112450.00	112450.00
3	Accessories for 11/0.4 KV Plinth mounted 63 KVA S/S with double disk arrangement and 5 Nos. earthing in No. 4 GI wire 1 No. GI flat earthing for Neutral alongwith LT Distribution Box with MCCB arrangement.	No	1	203815.40	203815.40
4	4 way service Distribution Box with kitkat fuse and Aluminium Busbar.	No	2	3005.60	6011.20
5	Acessories for 11 KV stud pole on 9 Mtr. Long RS Joist Pole(Except cost of pole)	No	1	2790.72	2790.72
6	LT Distribution Box with MCCB,Aluminium Bus bar for single bay with kitkat Fuse for 63 KVA S/S	No	1	24917.92	24917.92
7	3 core 50 sq. mm LT PVC cable	Mtr.	30	276.08	8282.40
8	LT 3 Ph 5W Line with 50 sq. mm AB cable using 9 Mtr. Long Joist Pole.(Excluding cost of pole)	Km	0.25	241205.90	60301.48
A	TOTAL MATERIAL COST IN RS				<b>613332.00</b>
B	Stock,storage and insurance (@3% on A)				<b>18399.96</b>
C	TOTAL RS.				<b>631731.95</b>
D	T&P @ 2% of C				<b>12634.64</b>
E	Contingency @ 3% of C				<b>18951.96</b>

F	Transportation @ 7.5% of C				<b>47379.90</b>
G	Erection charges of Transformer @ 5% of trnsformer and joist pole				<b>15821.46</b>
H	Erection charges of PSc Pole@ 20%				
I	Erection charges for other materials@ 10%				<b>31530.27</b>
	Total Rs.Part-A				<b>758050.18</b>
9	Cost of fencing	No	1	104661.02	104661.02
10	Padding and concreting material for support	No	8	2837.97	22703.76
11	Dismantling of 250 KVA DTR	No	1	5863.69	5863.69
12	Concreting of stay	No	6	1652.54	9915.24
13	Plinth for 63 kVA Transformer	No	1	22033.90	22033.90
	Total Rs.				<b>923227.79</b>
	Cess @1%				<b>9232.28</b>
	Total Estimated Cost				<b>932460.07</b>
	Total Estimated Cost in Figures				<b>932,460.00</b>
EXCESS	<input type="checkbox"/> LESS <input type="checkbox"/> (Please Tick)			_____ %	
	Quoted Amount in Figure				
	Quoted Amount in word				

N:B- The Estimated cost is exclusive of GST .

**Signature of Tenderer with seal**

Sd/-  
Asst. Project Manager (Elect)

Sd/-  
D.M (Elect) I/C

Sd/-  
DGM Engg.(Elect.)