## THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD. JANAPATH, BHOINAGAR, BHUBANESWAR - 22

[Electrical Division]

Ph: 0674-2541545, 2542921, Fax: 0674-2541543

E-mail:-pmelectricalophwc2025@gmail.com, Website: www.ophwc.com/www.ophwc.nic.in

## PRICE BID FOR THE WORK UNDER SL. NO:-08 AS PER IFB

NAME OF THE WORK :- EXECUTION OF EXTERNAL ELECTRIFICATION WORK & SITC OF PUBLIC INFORMATION SYSTEM AT GUMMA BUS STAND (ABS-C TYPE) (PHASE-I) IN THE DISTRICT OF GAJAPATI.

BID REF NO	D 61/PM/ELECT/OPHWC/2024-25				
NAME & ADDRESS OF THE FIRM					
	SCHEDULE OF V	WORKS_			
				Estimated Cost in Rs.	
Sl. No.	Description of work	Unit	Qty.	RATE IN RS.	AMOUNT IN RS.
PART-A	EXTERNAL ELECTRIFICATION WORK				
I	UPGRADATION OF S/S FROM 25 KVA TO 63 KVA S/S-1 NO.				
1	63 KVA 11/0.4 KV (AL) Transformer with BIS Energy Level-II	No	1	112450.00	112450.00
2	LT Distribution Box with MCCB, Aluminium Bus Bar for single- bay with Kitkat fuse for 63 KVA S/S.	No	1	23818.60	23818.60
3	40 mm Nominal bore GI Pipe Medium gauge(3.25 mm thickness) earthing device 3 mtrs long	No	2	1428.00	2856.00
4	GI flat 25x6 mm for earthing	Kg	30	102.00	3060.00
5	LT 1 core 95 sq. mm LT XLPE cable	Mtr.	40	191.10	7644.00
6	GI Nuts and Bolts of assorted size	Kg	8	106.08	848.64
7	Sundries (Al. binding tape, insulation tape, paint etc.)	LS	1	500.00	500.00
	A.Sub Total Rs.				1,51,177.2
В	Stock,storage and insurance (@3% on A)				4535.3
С	TOTAL RS.				155712.5
D	T&P @ 2% of C				3114.2
E	Contigency @ 3% of C				4671.3
F	Transportation @ 7.5% of C				11678.4
G	Erection charges @ 10% on others ,5% on Dist. Transformers/Joist Pole/WPB Poles and 20% on PSC poles				9780.0
Н	TOTAL RS.				184956.7
8	Materials for Masonary work for earth pit, charcoal, salt etc. including construction of earthing chamber (size -2"x2") and RCC slab cover.	No	2	1600.00	3200.00
	Sub Total Rs.				1,88,156.72
	PART-B (PUBLIC INFORMATION SYSTEM)				

	40001126	1	1		
1	providing and fixing 8 SWG(4mm)dia copper wire on surface or in recess for loop earthing as required.	RFT	80	31.50	2520.00
2	40001703 Supply and fixing of 2 way single door MCB box with 1 no 32 AMP DPMCB with sheet steel encloser, distribution board, on surface /recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnection, phosphate and power painted including earthing etc as required.  Make of MCB -Legrand/L &T/ABB /SCHNIDER.	NO	2	903.47	1806.94
3	40001993 Supply and laying of 4Sqmm 3 Core Cupper Cable 20 mm dia non-metalic heavy duty flexible conduit 1.6 mm thick. (Make of wire Finolex/L &T/Anchor/Havels/V Guard).	MTR	50	164.88	8244.00
4	40002149 Supply and laying of 6 sq.mm 4 core copper flexible cable Panel to AC out door Unit.(Make of Cable-Finolex/Havells/ Polycab).	MTR	50	267.22	13361.00
5	40002163 Supply and fixing of 6 sq.mm 04 core PVC Al. Arm Cableof 1.1 KV grade end termination.	SET	4	150.00	600.00
6	40002360 Supply and fixing of 40mm dia HDPE pipe -PE 80 grade PN-6. 2.0 wall thickness.	MTR	100	93.00	9300.00
7	40002497 Supply of outdoor type auxillary panel board made out from 20guage thick CR Sheet duly painted with clamping arrangement to be fixed on street light pole equipped with 04 nos bus bar 03 nos indication lamp with 1 No toggle switch ,1 no timer switch , 1 No Stud type 4 way terminal I/P) 63 Amp ) 1 No 63A TPN MCB, 1 No 3 Pole Contractor 65 A, 1 No Single Pole MCB 10A, 3 Nos 16 amp TPN MCB , 3 Nos Stud type , 4 way terminal (O/P) 63A A with earthing arrangement. [Make-(a) MCB /MCCB - Legrand/ Schnider/L &T/ ABB, (b) Volt meter, Ammeter-AE/CAPPA, (c) all other accessories ISI mark].	NO	2	23000.00	46000.00
8	40008291 Supply and fixing of Earthing with GI earth pipe 3 meter long 40 mm dia Heavy Duty TATA make including accessories and providing masonary enclosure with cover plate having locking arrangement and water pipe etc with charcoal and salt as required. (Minimum 1.5 mtr distance from building & 3 mtr distance from earthing to earthing).	NO	4	3730.35	14921.40
9	40008505 Supply & fixing of cat-6 UTP cable,4 pair,23AWG,FRPVC CM for LAN wiring with conduit pipe / PVC casing caping / under floor G.I. Tunk line. MAKE- D-LINK(MODEL NO-NCB-C6UGRYR)/DIGISOL/MOLEX).	MTR	100	57.74	5774.00

10	40010417 LED Display Board 12'6" LX6'3" H/10'LX6'3"H/8'0"LX6'3"HP 6 pixel density 160000 dots/sqm module resolution128x64 dots frame frequency 60Hz single LED unit pixel ,brightness 800-1000cd/sqm,gray scale up to 16bit /2.81 billion,optimum viewing angle 140x120,input voltage 220V AC, operating tempreature 200C to 500C,Cabinet size 960mmx960mm die cast ,english/odia /any language for text,video,image,outdoor active LED video fixed on unipole structure with ACB box with supply and installation. Thickness of the screen>120mm wall(BIS certified module). Make of LED: NATION STAR SMP.	SFT	60	10418.00	625080.00
11	40010419 Novastar TB 40 processor with 4G module(BIS certified module),Novastar IND 528 receiving card,cloud based software inbuilt,LAN/Cloud data entry system having multiscreen playback synchronization mechanism. (Make-Novastar TB 40).	SET	2	22727.00	45454.00
12	40010425 Fixing of frame unipole structure 8'6"X6'3" with ACP box for supporting LED sign Board 40 x 40 x 3 mm sa SS 304 grade pipe and top plate for pole 580 x 500 x 12 mm with base plate 450 x450 x 20mm and single pole size 275× 5 x 3000 mm working platform made by 25 x 25 x 3 mm SS-304 grade square pipe. Panel size 768 x 768 mm of ACP work Ahuja 100 watt speaker.SS-304 -JINDAL/NIPPON STEEL of Premium quality.	SET	1	137273.00	137273.00
13	40010428 LED Display Board 12.2' length X 4.2'height.,10.6' length X 4.2'height. Indoor P 2.5 pixel, density 160000 dots/sqm, module resolution 128x64 dots, module dimension 320 x160x15 mm frame frequency 60hz, single LED unit pixel, brightness 800-1000cd/sqm, gray scale up to 16bit/2.81 billion, optimum viewing angle 140x120, input voltage 220V AC, operating temperature 20°C to 50°C, cabinate size 320mmX160mm magnetic module, english/ odiya/ any language for text, video, image, Indoor Active LED Video fixed on wall mounting with steel structure supply and installation Thickness of the screen>60mm Wall. (BIS certified module). Make of LED: NATION STAR SMP.	SFT	45	10909.00	490905.00
14	40011214 Fixing of frame structure for supporting Indoor LED board made by 40x40x3 mm square pipe.	SET	1	90000.00	90000.00
	Total Rs.				1491239.34
	Total Rs.(PART-A+PART-B)				16,79,396.06
	Cess @ 1%				16,793.96
	Total Estimated Cost				16,96,190.02
	Total Estimated Cost in Figures				16,96,190.00
EXCESS	LESS Please Tick)			%	
	Quoted Amount in Figure				
	Quoted Amount in word				
	NID TI E 1 COCT				

## THREE YAER'S COMPREHENSIVE ANNUAL MAINTENANCE CONTRACT CHARGES OF THE PUBLIC <u>INFORMATION</u> <u>SYSTEM AFTER COMPLETION OF TWO YEARS OF WARRANTY PERIOD</u>

SL NO.	PERIOD	QUOTED PRICE (Rs)	% OF GST
1	1ST YEAR		
2	2ND YEAR		
3	3RD YEAR		

Signature of Tenderer with seal

Sd/-Asst. Project Manager (Elect) Sd/-D.M (Elect)

Sd/-Project Manager (Elect)