THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD. JANAPATH, BHOINAGAR, BHUBANESWAR - 22

[Electrical Division]

Ph: 0674-2541545, 2542921, Fax: 0674-2541543

E-mail:-pmelectricalophwc2021@gmail.com, Website: www.ophwc.nic.in

PRICE BID FOR THE WORK UNDER SL. NO:- 03 AS PER IFB

NAME OF THE WORK :- EXECUTION OF EXTERNAL ELECTRIFICATION WORK FOR POWER SUPPLY TO AMA BUS STAND AT KHARIAR, UNIT-III IN THE DISTRICT OF NUAPADA.

BID REF NO :- 11/PM/ELECT/OPHWC/2024-25

| NAME & |
|-------------|
| ADDRESS |
| OF THE |
| FIRM |

SCHEDULE OF WORKS

| | | | | Estimated Cost in Rs. | |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|-----------------------|---------------|
| | | | | | |
| Sl. No. | Description of work | Unit | Qty. | RATE IN RS. | AMOUNT IN RS. |
| 1 | 11 Mtr. Long 150x150 mm RS Joist Pole(34.6 Kg/Mtr.)For Line, S/S,DP. | No | 5 | 32160.70 | 160803.50 |
| 2 | 11/.04 KV 250 KVA Transformer(Star-2,BIS/EEL-2) | No | 1 | 709431.39 | 709431.39 |
| 3 | Construction of 11/0.4 KV Plinth mounted 250 KVA S/S ON 11 Mtr. Long RS Joist Pole with double disc arrengement and 5 Nos. GI Flat earthing alongwith LT Distribution box with MCCB arrangement. | No | 1 | 188367.88 | 188367.88 |
| 4 | Construction of 3 Ph 3W 11 KV Line with single core 55 sq. mm XLPE Insulated covered conductor on 11 Mtr. Long Joist Pole. | Km | 0.07 | 589593.95 | 41271.58 |
| 5 | Acessories for tapping arrangement of 11 KV Line on 11 Mtr. Long RS Joist Pole . | No | 1 | 19222.91 | 19222.91 |
| 6 | Acessories for DP metering unit on 11 Mtr. Long RS Joist Pole with earthing arrangement and control cable. | No | 1 | 60819.85 | 60819.85 |
| А | TOTAL MATERIAL COST IN RS | | | | 1179917.11 |
| В | Stock, storage and insurance (@3% on A) | | | | 35397.51 |
| С | TOTAL RS. | | | | 1215314.62 |
| D | T&P @ 2% of C | | | | 24306.29 |
| E | Contigency @ 3% of C | | | | 36459.44 |
| F | Transportation @ 7.5% of C | | | | 91148.60 |

| | Erection charges of Joist Pole and | | | | |
|--------|------------------------------------------|----|----|-----------|--------------|
| G | Transformer @ 5% | | | | 44817.10 |
| Н | Erection charges of PSc Pole@ 20% | | | | |
| | Erection charges for other materials@ | | | | |
| I | 10% | | | | 31897.27 |
| | Total Rs.Part-A | | | | 14,43,943.32 |
| 7 | Cost of Fencing with metal spreading | No | 1 | 104661.02 | 104661.02 |
| 8 | Concrete materials for stay anchor plate | No | 10 | 1652.54 | 16525.40 |
| 9 | Padding and Concreting materials for | | | | |
| | support | No | 5 | 2837.90 | 14189.50 |
| 10 | Plinth for the S/S | No | 1 | 22033.89 | 22033.89 |
| 11 | Road crossing Guarding | No | 1 | 7932.30 | 7932.30 |
| | Total Rs.Part-B | | | | 165342.11 |
| | TOTAL RS. | | | | 16,09,285.43 |
| | Cess @1% | | | | 16092.85 |
| | Total Estimated Cost | | | | 1625378.28 |
| | Total Estimated Cost in Figures | | | | 16,25,378.00 |
| EXCESS | LESS Please Tick) | % | | | |
| | Quoted Amount in Figure | | | | |
| | Quoted Amount in word | | | | |

N:B- The Estimated cost is exclusive of GST.

Signature of Tenderer with seal

Sd/-Asst. Project Manager (Elect) Sd/-D.M (Elect) I/C

Sd/-Project Manager(Elect)