THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD. JANAPATH, BHOINAGAR, BHUBANESWAR - 22

[Electrical Division]

Ph: 0674-2541545, 2542921, Fax: 0674-2541543

E-mail:-pmelectricalophwc2021@gmail.com, Website: www.ophwc.nic.in

PRICE BID FOR THE WORK UNDER SL. NO :- 01 AS PER IFB

NAME OF THE WORK: - EXECUTION OF EXTERNAL ELECTRIFICATION WORK (SHIFTING AND RECONSTRUCTION OF 11 KV LINE) AT AMA BUS STAND, PAIKAMAL IN THE DISTRICT OF BARGARH.

BID REF NO:- 12/PM/ELECT/OPHWC/2024-25

NAME &
ADDRESS
OF THE
FIRM

SCHEDULE OF WORKS

				Estimated Cost in Rs.		
SI. No.	Description of work	Unit	Qty.	RATE IN RS.	AMOUNT IN RS.	
1	13 Mtr. Long 150x150 mm RS Joist Pole(34.6 Kg/Mtr.)	No	6	38008.10	228048.60	
2	Construction of 3 Ph 3W 11 KV Line with 100 sq. mm XLPE Insulated covered AAA conductor on 13 Mtr. Long Joist Pole.	Km	0.90	117000.00	105300.00	
3	11 KV Intermediate Pole(Excluding Pole)	Nos	4	5349.50	21398.00	
4	11 KV stay set	Set	3	3918.20	11754.60	
5	Acessories for 11 KV Single pole cut point on 13 Mtr. Long RS Joist Pole with double disc arrangement(Except cost of	N		25050 50	55001.56	
6	pole)	No No	1	27950.78 4763.20	55901.56 4763.20	
	11 KV Guarding for Road Crossing TOTAL MATERIAL COST IN RS	NO	1	4/03.20	427165.96	
В	Stock, storage and insurance (@3% on A)				12814.98	
С	TOTAL RS.				439980.94	
D	T&P @ 2% of C				8799.62	
E	Contigency @ 3% of C				13199.43	
F	Transportation @ 7.5% of C				32998.57	
G	Erection charges of Joist Pole and Transformer @ 5%				11744.50	
Н	Erection charges of PSC Pole@ 20%					
I	Erection charges for other materials@ 10% Total Rs.Part-A				20509.09 5,27,232.15	
7	Dismantling cost of 11 KV Line	Km	0.2	15450.00	3090.00	

	Total Rs.Part-B		3090.00
	TOTAL RS.		5,30,322.15
	Cess @1%		5303.22
	Total Estimated Cost		535625.37
	Total Estimated Cost in Figures		5,35,625.00
EXCESS	LESS Please Tick)	%	
	Quoted Amount in Figure		
	Quoted Amount in word		

N:B- The Estimated cost is exclusive of GST.

Signature of Tenderer with seal

Sd/-Asst. Project Manager (Elect) Sd/-D.M (Elect) I/C

Sd/-Project Manager(Elect)