

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.**JANAPATH, BHOINAGAR, BHUBANESWAR - 22****[Electrical Division]****Ph: 0674-2541545, 2542921, Fax: 0674-2541543****E-mail :- pmelectricalophwc2025@gmail.com, Website: www.ophwc.com****PRICE BID FOR THE WORK UNDER SL. NO :- 01 AS PER IFB****NAME OF THE WORK :- EXECUTION OF EXTERNAL ELECTRIFICATION WORK FOR POWER SUPPLY TO ST. JOHN AMBULANCE OFFICE BUILDING AT BJB NAGAR, BHUBANESWAR IN THE DISTRICT OF KHURDA.****BID REF NO :- 71/PM/ELECT/OPHWC/2025-26**

NAME & ADDRESS OF THE FIRM	
---	--

SCHEDULE OF WORKS

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
I	CONSTRUCTION OF 11 KV LINE .				
A	11 KV CUT POINT WITH 90 DEGREE ANGLE				
1	WPB(GI) Pole 160x152 mm (13 Mtr. Long ,30.44 Kg/Mtr.)	No	1	43,287.99	43,287.99
2	Straight Cross Arm 100X50X6mm, 9.56 KG/Mtr., each channel length 1.2 mtr., 4 no's channel required =(4x9.56x1.2)	Kg	45.888	106.50	4,887.07
3	Fish Plate 50x6 mm., 2.36 kg/Mtr., each 0.280 mtr. length, 16 no's required	Kg	10.5728	106.50	1,126.00
4	Straight Cross Arm 100X50X6mm, 9.56 KG/Mtr., each channel length 0.306 mtr., 4 no's channel required =(42x9.56x0.306)	Kg	11.7014	106.50	1,246.20
5	Danger plate	No	1	113.60	113.60
6	Back clamp for Danger Plate 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 1 Nos=(1x0.59x0.510)	Kg	0.3009	106.50	32.05
7	GI barbed wire/Anticlimbing device	No	3	113.60	340.80
8	Back clamp for Anticlimbing Device 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 4 Nos=(4x0.59x0.510)	Kg	1.2036	106.50	128.18
9	11 KV pin insulator polymer	Set	4	284.00	1,136.00
10	H W fitting(B&S) 70KN, 3Bolt	No.	6	497.00	2,982.00
11	Disc insulator (B&S) 70 KN polymer	No.	6	1,633.00	9,798.00
12	Earthing of Support (Coil Type)	No	1	235.72	235.72
13	No. 8 GI wire (dia 4.6 mm)0.131 Kg/Mtr.-2 Mtr. For connecting pole with coil earthing	Kg	0.262	106.50	27.90
14	Wedge connector for 55 sq. mm conductor	No	6	100.00	600.00
15	Polycarbonate Bird Guard	No	10	29.40	294.00
16	H.T. Stay clamp, 50x8 mm. Flat(GI), 3.14Kg/Mtr., 0.551 Mtr. Length, 2 no's qty. required (1 Pair)	EA	2	177.50	355.00
17	H.T. Stay set (Complete)	SET	2	1,491.00	2,982.00

18	H.T. Stay Insulator Type-C	EA	2	71.00	142.00
19	7/10 SWG Stay Wire 15kg /stay	KG	30	106.50	3,195.00
20	GI Nut , Bolt & Washer of different sizes (7.433 Kg each cut pole)	Kg	7.433	110.76	823.28
21	Yellow colour paint for Background(GIS Numbering & Zebra stripping)for Background	Ltr	2	216.00	432.00
22	Black paint (GIS Numbering & Zebra stripping)	Ltr	0.5	312.40	156.20
A	A. Sub total				74,321.00
B	B. Stock, Storage & Insurance @ 3% of A				2,229.63
C	Sub Total (C=A+B)				76,550.63
D	T&P @ 2% of C				1,393.53
E	Contingency @ 3% of C				2,296.52
F	Transportation @ 7.5% of C				5,741.30
		Erection Charges @ 5% on poles			2,229.33
G	Erection Charges @ 10%				2,508.97
H	Total				90,720.27
23	Fixing of complete 11KV line Complete stay set includes 1) Turn Buckle Assembly 2) Stay Rod & Stay plate 3) Stay Insulator 4) Stay Wire. 5)Stay clamps with Nuts & bolts BA will do the excvation including excvation, supply of 0.5Cum cement concrete foundation 1:2:4 size (500mmx500mmx800mm) using 20mm BHG metal with all labour and material as per TPCODL Drawing & Standard.	No	2	2,301.53	4,603.06
24	Concreting ratio 1:1.5:3(M-20 Grade) (500mmX500mmX1800mm) = 0.45Cu.mtr(Per Pole)	Cum	0.55	6,648.85	3,656.87
25	Couping ratio 1:1.5:3(M-20 Grade) with dimension (500X500X450)= 0.1125 Cu mtr(Per Pole)	Cum	0.1125	6,648.85	748.00
	Total Material + Services Cost (J+K)				99,728.19
C	11 KV PIN POINTS WITH WPB				
1	55 sq. mm AAAC	Km	0.03	42,600.00	1,316.34
A	A. Sub total				1,316.34
B	B. Stock, Storage & Insurance @ 3% of A				39.49
C	Sub Total (C=A+B)				1,355.83
D	T&P @ 2% of C				27.12
E	Contingency @ 3% of C				40.67
F	Transportation @ 7.5% of C				101.69
		Erection Charges @ 5% on poles			
G	Erection Charges @ 10%				135.58

H	Total				1,660.89
II	INSTALLATION OF 63 KVA S/S.				
1	WPB GI Pole160X152(11 Mtr. Long ,30.44 Kg/Mtr.)	No	2	36,804.27	73,608.54
2	Top channel GI 100x50x6 mm 3000 mm Long(9.56 kg/Mtr.,2 Nos.)	Kg	57.36	106.50	6,108.84
3	Fish Plate 50x6 mm ,2.36 Kg/Mtr.,each 0.280 Mtr., 6 nos. required	Kg	3.9648	106.50	422.25
4	AB switch mounting channel 75x40x4.8 mm GI channel, 3000 mm Long (7.14 kg/mtr,2 Nos.)	Kg	42.84	106.50	4,562.46
5	AB witch side support channel 100x50x6 mm GI channel (0.35Mtr Long)(9.56 kg/mtr,2 Nos.)	Kg	6.69	106.50	712.49
6	Channel support for down pipe 75x40x4.8 mm GI channel(7.14 kg/mtr,2 Nos.)each channel length 0.8 Mtr.	Kg	5.711	106.50	608.22
7	HG/DO fuse Mounting channel 75x40x4.8 mm GI channel(3000 mm Long) (7.14 kg/mtr,2 Nos.)	Kg	42.84	106.50	4,562.46
8	Cantilever suport channel75x40x4.8 mm GI channel(810 mm Long,2 Nos.)(7.14 kg/mtr,2 Nos.)	Kg	11.57	106.50	1,232.21
9	Cantilever suport angle 50x50x6 mm GI (1282 mm Long)(4.5 kg/mtr,2 Nos.)	Kg	11.54	106.50	1,229.01
10	Transformer Base GI Channel 100 X 50 X 6 MM (3000 mm long) (9.56Kg./Mtr, 2 No's.) (Each 2x3.000x9.56= 57.36 Kg)	Kg	57.36	106.50	6,108.84
11	Transformer Base Support GI Channel 100 X 50 X 6 MM (515 mm long) (9.56Kg./Mtr, 2 No's) (Each 2x0.515x9.56= 9.85Kg)	Kg	9.85	106.50	1,049.03
12	Transformer Belting Angle 50 X 50 X 6MM GI (3000 mm long)(4.5Kg./Mtr, 2 No's) (Each 2x3.0x4.5 Kg)	Kg	27	106.50	2,875.50
13	Transformer Belting Support Angle 50 X 50 X 6MM GI (580 mm long)(4.5Kg./Mtr,2 No's) (Each 2x0.580x4.5= Kg)	Kg	5.22	106.50	555.93
14	LTDB Mounting Angle 50 X 50 X 6MM GI (1000 mm long)(4.5Kg./Mtr, 2 No's) (Each 2x1x4.5 Kg)	Kg	9	106.50	958.50
15	50x6mm Flat(GI) for earthing, 2.36kg/mtr., (2.5x7 mtr. For mesh formation, 12 Mtr. For LA and 2.5 mtr. For raising, 11 mtr for AB switch, 2.8 mtr for HG Fuse, 5x2 mtr. for DTR Nutral, (1.3+4.5) mtr. For DTR Body, 0.500 mtr for LTDB & AB Switch operating handle, 3 mtr. for Fencing) (Each 65.6x 2.36= 154.81 Kg)	Kg	154.81	106.50	16,487.27
16	63 KVA , 11/ 0.4 KV (AL) Transformer, BIS Energy Loss level II, Ammendment-4	No	1	141,308.92	141,308.92
17	LT Distribution Box with MCCB, Aluminium Busbar of single Bay with kit kat fuse for 63 KVA S/S	No	1	26,017.24	26,017.24
18	55 SQ.MM. AAAC XLPE Covered Conductor	Mtr	50	99.74	4,987.00
19	4 Cx 95 mm2 LT XLPE Cable(Armoured) - FOR 63 KVA Trf.	Mtr	15	499.41	7,491.15
20	11 KV AB switch (200 Amp, 3 pole)	Set	1	10,437.00	10,437.00
21	11 KV HG Fuse (200 Amp, 3 pole)	Set	1	8,690.00	8,690.00
22	Wedge connector for 55 sq. mm conductor	EA	6	100.00	600.00

23	Polycarbonate Bird Guard	No	6	29.40	176.40
24	11 KV Disc insulator polymer type 70 KN	No	3	1,633.00	4,899.00
25	11 KV H/W fitting polymer type	Pair	3	497.00	1,491.00
26	11 KV LA (12KV,10 KA)station class-2	No	3	5,041.00	15,123.00
27	11 KV Pin Insulator polymer type	No	3	284.00	852.00
28	HT Stay Set (Complete)	Set	2	1,491.00	2,982.00
29	HT Stay Insulator	No.	2	177.50	355.00
30	HT Stay Clamp(1.95 K.g/Pair)	Pair	2	71.60	143.20
31	7/10 SWG Stay Wire	KG	30	106.50	3,195.00
32	GI Pipe for earthing 40mm dia 3mtr long	No	7	1,491.00	10,437.00
33	GI Nut, Bolt & washers of different sizes	Kg	25	110.76	2,769.00
34	GI barbed wire/Anticlimbing device	No	6	113.60	681.60
35	Back clamp for Anticlimbing Device 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 4 Nos=(4x0.59x0.510)	Kg	2.4072	106.50	256.37
36	Danger plate	Kg	2	113.60	227.20
37	Back clamp for Danger Plate 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 1 Nos=(1x0.59x0.510)	Kg	0.6018	106.50	64.09
38	Name Plate	No	1	113.60	113.60
	Structure Numbering and marking				
39	Yellow colour paint for Background	Ltr	2	216.00	432.00
40	Black colour paint for numbering	Ltr	1	312.40	312.40
A	A. Sub total				365,122.70
B	B. Stock, Storage & Insurance @ 3% of A				10,953.68
C	Sub Total (C=A+B)				376,076.38
D	T&P @ 2% of C				7,014.71
E	Contingency @ 3% of C				11,282.29
F	Transportation @ 7.5% of C				28,205.73
G	Erection Charges @ 5% for transformer and joist pole cost including stock, storage & insurance @3%				11,068.25
H	Erection Charges @ 20% on PSC Poles				
I	Erection Charges @ 10% for other materials				12,937.04
J	Total				446,584.40
41	Concreting Ratio 1:1:5:3(500 mmx500mmx1800 mm)=0.45 Cu. Mtr.	Cum	0.9	6,648.85	5,983.97
42	Couping Ratio 1:1:5:3 with dimension(500 mmx500mmx450 mm)=0.1125 Cu. Mtr.	u. Mtr	0.226	6,648.85	1,502.64
43	PCC ratio 1:3:6(M-10) grade for DSS area (3.5x2.5x0.1)=0.875 Cu Mtr.	u. Mtr	1.5	5,247.48	7,871.22
44	Fixing of stay set with 0.5 cum cement concret foundation 1:3:6 size (900x 600x900 mm) using 40 mm BHG metal with all labour and material except stay wire, stay set,stay insulator.	No	2	2,301.53	4,603.06

45	Construction of earthing chamber including installation of earthing pipe.Making earthing chamber including excavation, soil treatment with betonide powder, calculation of earth resistance,including installation of 3 Mtr. GI Pipe 40/50 mm including welding of GI flat around pipe.	No	7	3,784.73	26,493.11
46	Laying of 4Cx95 sq.mm LT XLPE cable	Mtr.	15	47.87	718.05
47	Supply and Erection of GI fencing with Gate	Sq. Mtr.	16	3,682.44	58,919.04
48	Supply of AL Lugs suitable for 95 sq mm cable/conductor, Crimping with cable and Fixing/connecting include supply and erection of PVC Tape as per voltage requirement.	No	8	92.06	736.48
49	Supply and erection of double Compression Flameproof Type Glanding for armored Cable 3.5/4 core 50-95 sq. mm sqmm including making hole in Base plate and dressing of cable along with vermin proofing properly .Supply to be done as per TPCODL Spec and approved make dowells.	No	3	690.46	2,071.38
					108,898.95
	Sub total Rs				555,483.35
	Sub Total Rs.				656,872.43
	Cess @1%				6,568.72
	Total Estimated Cost				663,441.16
	Total Estimated Cost in Figures				663,441.00
EXCESS	☐ LESS ☐ (Please Tick)	In Figure _____ % In word _____%			
Quoted Amount in Figure					
Quoted Amount in word					

N:B- The Estimated cost is exclusive of GST .

Signature of Tenderer with seal

**Sd/-
Asst. Project Manager (Elect)**

**Sd/-
Dy. Manager (Elect)**

**Sd/-
Project Manager(Elect)**