

**THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.**  
**JANAPATH, BHOINAGAR, BHUBANESWAR - 22**  
**[Electrical Division]**

**Ph: 0674-2541545, 2542921, Fax: 0674-2541543**

**E-mail :- pmelectricalophwc2025@gmail.com, Website: www.ophwc.com /www.ophwc.nic.in**

**PRICE BID FOR THE WORK UNDER SL. NO :- 01 AS PER IFB**

**NAME OF THE WORK :- SITC OF PROTECTION SYSTEM FOR ELEVATOR INSTALLED AT ADMINISTRATIVE BUILDING OF THE DIRECTORATE OF PRINTING STATIONARY & PUBLICATION, ODISHA, MADHUPATNA, CUTTACK.**

**BID REF NO :- 03/PM/ELECT/OPHWC/2025-26**

**NAME  
&  
ADDRESS  
OF THE  
FIRM**

**SCHEDULE OF WORKS**

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
1	<b>40001012</b> Recessed wiring to submain in 4 x 6 sqmm FR PVC insulated single core multistrand copper conductor of ISI marked confirming to IS-694/1990 in 32 mm dia non metallic heavy duty flexible conduit 1.6 mm thick along with 2 x 2.5 sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required (Make of wire Finolex / Anchor / Havells/ V guard/KEI) CSR SL .No- 1.8.10)(Make of PVC pipe- AKG/NORPACK)	MTR	45	313.46	14105.70
2	<b>40009300</b> Supply and fixing of 4 way , single Door MCB Box with 1 No 40 Amp. 4P MCCB with sheet steel encloser , distribution board, on surface/ recess, complete with tinned copper bus bar , neutral bus bar, earth bar, din bar , detachable gland plate, interconnection , phosphate and power painted including earthing etc as required.( Sl. No- 2.3.,2.7, )Make-MCB-(Legrand/L&T/ABB/SCHNIDER/ANCHOR-PANASONIC)	SET	2	1566.06	3132.12

3	40011836 Supply and installation of 10KVA/10KW online high performance double conversion UPS system with three phase AC input and three phase AC output for 60 Min back up with IGBT based with unit power factor,inbuilt isolation transfromer,with parallel redundancy provision(PRS),built in phase sequence corrector,DC cable 7 Mtr,interlink SFU and SMF batteries back up of 60 minutes and MS rack for battery housing.MS rack for housing the batteries & link cable ,18 nos 12V 65AH SMF batteries with two years warranty on both UPS & battery (Make-UPS-Numeric (Model-HPi33evoFMI)/APC,Make-Battery-Exide/Quanta)	NO	1	465000	465000.00
4	40011838 Supply and Fixing of 63 Amp four pole changeover with SS enclosure & busbar including allaccessories and connections . [make-(a) - Legrand/ Schnider/Havells Crabtree/ ABB, all other accessories ISI mark]	SET	1	10678	10678.00
<b>Sub Total Rs.</b>					<b>492915.82</b>
<b>cess @1%</b>					<b>4929.16</b>
<b>Total Estimated Cost</b>					<b>497,844.98</b>
<b>Total Estimated Cost in Figures</b>					<b>497,845.00</b>
EXCESS	<input type="checkbox"/>	LESS	<input type="checkbox"/>	(Please Tick)	_____%
Quoted Amount in Figure					
Quoted Amount in word					

N:B- The Estimated cost is exclusive of GST .

Signature of Tenderer with seal

Sd/-  
Asst. Project Manager (Elect)

Sd/-  
Dy. Manager (Elect)

Sd/-  
Project Manager (Elect)