

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.**JANAPATH, BHOINAGAR, BHUBANESWAR - 22****[Electrical Division]****Ph: 0674-2541545, 2542921, Fax: 0674-2541543****E-mail :- pmelectricalophwc2025@gmail.com, Website: www.ophwc.com****PRICE BID FOR THE WORK UNDER SL. NO :- 05 AS PER IFB****NAME OF THE WORK :- EXECUTION OF EXTERNAL ELECTRIFICATION WORK FOR POWER SUPPLY TO KORUA POLICE STATION IN THE DISTRICT OF KENDRAPADA.****BID REF NO :-65/PM/ELECT/OPHWC/2025-26****NAME &
ADDRESS
OF THE
FIRM****SCHEDULE OF WORKS**

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
I	CONSTRUCTION OF 11 KV LINE .				
B	11 KV PIN POINTS WITH WPB				
1	55 sq. mm AAAC	Km	0.1545	40,800.00	6,303.60
A	A. Sub total				6,303.60
B	B. Stock, Storage & Insurance @ 3% of A				189.11
C	Sub Total (C=A+B)				6,492.71
D	T&P @ 2% of C				129.85
E	Contigency @ 3% of C				194.78
F	Transportation @ 7.5% of C				486.95
	Erection Charges @ 5% on poles				
G	Erection Charges @ 10%				649.27
H	Total				7,953.57
II	INSTALLATION OF 63 KVA S/S.				
1	63 KVA , 11/0.4 KV (AL) Transformer BIS Energy Level-II	No	1	152,486.81	152,486.81
2	LT Distrubution Box with MCCB, Aluminim Busbar of single Bay with kit kat Fuse for 63 KVA S/S.	No	1	24,917.92	24,917.92
3	55 sq. mm All Alloy conductor-PVC insulated	Mtr	50	55.24	2,762.00
4	4Cx95 sq. mm LT XLPE cable	Mtr	20	438.71	8,774.20
5	GI Pipe for earthing 40mm dia 3mtr long	No	7	1,428.00	9,996.00
6	GI Nut, Bolt & washers of different sizes	Kg	25	106.08	2,652.00
7	GI barbed wire/Anticlimbing device	No	6	108.80	652.80
8	Back clamp for Anticlimbing Device 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 4 Nos=(4x0.59x0.510)	Kg	2.4072	102.00	245.53
9	Danger plate	Nos.	2	108.80	217.60
10	Back clamp for Danger Plate 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 1 Nos=(1x0.59x0.510)	Kg	0.6018	102.00	61.38
11	Name Plate	No	1	108.80	108.80

	Structure Numbering and marking					
12	Yellow colour paint for Background		Ltr	2	167.46	334.92
13	Black colour paint for numbering		Ltr	1	299.20	299.20
A	A. Sub total					203,509.17
B	B. Stock, Storage & Insurance @ 3% of A					6,105.28
C	Sub Total (C=A+B)					209,614.44
D	T&P @ 2% of C					4,192.29
E	Contingency @ 3% of C					6,288.43
F	Transportation @ 7.5% of C					15,721.08
G	Erection Charges @ 5% for transformer and joist pole cost including stock, storage & insurance @3%					7,853.07
H	Erection Charges @ 20% on PSC Poles					
I	Erection Charges @ 10% for other materials					4,225.72
J	Total					247,895.04
14	Laying of 4Cx95 sq.mm LT XLPE cable	Mtr.	20	47.87	957.40	
15	Supply of AL Lugs suitable for 95 sq mm cable/conductor, Crimping with cable and Fixing/connecting include supply and erection of PVC Tape as per voltage requirement.	EA	8	92.06	736.48	
16	Supply and erection of double Compression Flameproof Type Glanding for armored Cable 3.5/4C 50-95sqmm including making hole in Base plate and dressing of cable along with vermin proofing properly .Supply to be done as per TPCODL Spec and approved make dowells.	EA	3	690.46	2,071.38	
					3,765.26	
	Sub total Rs					251,660.30
	Sub Total Rs.					259,613.87
	Cess @1%					2,596.14
	Total Estimated Cost					262,210.00
	Total Estimated Cost in Figures					262,210.00
EXCESS	☐ LESS ☐ (Please Tick)		In Figure _____ % In word _____ %			
Quoted Amount in Figure						
Quoted Amount in word						
N:B- The Estimated cost is exclusive of GST .						

Signature of Tenderer with seal

**Sd/-
Asst. Project Manager (Elect)**

**Sd/-
Dy. Manager (Elect)**

**Sd/-
Project Manager (Elect)**