

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.
JANAPATH, BHOINAGAR, BHUBANESWAR - 22
[Electrical Division]
Ph: 0674-2541545, 2542921, Fax: 0674-2541543
E-mail :- pmelectricalophwc2025@gmail.com, Website: www.ophwc.com

PRICE BID FOR THE WORK UNDER SL. NO :- 01 AS PER IFB

NAME OF THE WORK :- EXECUTION OF EXTERNAL ELECTRIFICATION WORK TO CATER POWER SUPPLY TO 6-F+12-E TYPE STAFF QUARTERS AT DIST. HDQRS., CHHATRAPUR IN THE DISTRICT OF GANJAM.

BID REF NO.- 46/PM/ELECT/OPHWC/2026-27

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
	PART-A				
I	Construction of 3P 3W Line with 50mm² XLPE Cable - 0.050 Km				
1	Pole WPB GI 160x152 11 Mtr	No	1.00	27300.82	27,300.82
2	11KV V cross arm (10.5Kg each)	No	1.00	851.00	851.00
3	GI Back Clamp for V cross Arm (0.8kg each)	No	1.00	140.00	140.00
4	11 KV F clamp (GI)	No	1.00	135.00	135.00
5	11 KV 5KN Polymer pin insulator	No	3	140.00	420.00
6	12KV 10KA 11KV Lighting Arrestor Station CI-II.	No	3.00	1960.00	5,880.00
7	(75x40x6) mm GI Channel, 1.2 Mtr Long, 02 Nos for road support of Las.	Kg	16.32	78.00	1,272.96
8	Heat shrinkable joning kit suitable for 3Cx50 mm ² 11KV XLPE Cable (outdoor Type)	No	4.00	1610.18	6,440.71
9	11KV AL 3Cx50 Sq.mm XLPE Round Armoured.	Mtr	52.50	859.00	45,097.50
10	7/12 SWG GI Stay Wire,	Kg	16.07	79.00	1,269.14
11	11 KV XLPE cable clamp to hold support wire.	No	52.50	22.77	1,195.38
12	Pole Clamp for Eye hook for XLPE cable.	Pair	4.00	240.00	960.00
13	Eye hook for XLPE cable	No	4.00	75.00	300.00
14	Suspension Clamp for XLPE cable	Pair	4.00	140.00	560.00
15	Conductor dead end clamp suitable for bare messenger XLPE Aerial bunched cable (25-70 mm)	No	2.00	217.00	434.00
16	GI Flat 25 x6 mm for earthing	Kg	24.00	72.00	1,728.00
17	GI Pipe earthing 40 mm dia medium gauge (3.25mm thickness) 3 mtr long	No	3.00	1300.00	3,900.00
18	Earthing coil	No	1.00	164.00	164.00
19	GI Nut , Bolt & Washer of different sizes	Kg	5.00	74.00	370.00
20	100x50x6mm, MS Channel for straight cross arm (1.2mx16 pcs) (9.2kg/mtr)+(0.2mx0 pcs) 99.2kg/mtr) for tapping & cut point pole.	Kg	22.08	78.00	1,722.24

21	Anticlimbing Device (GI barbed with 3kg per support)	Kg	3.00	74.00	222.00
22	Back clamp for Anticlimbing Device 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 4 Nos=(8x0.59x0.510)	Kg	0.60	78.00	46.80
23	Danger Plate	No	1.00	180.00	180.00
24	Back clamp for Danger Plate 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 1 Nos=(2x0.59x0.510)	Kg	0.60	78.00	46.80
25	Sundries	LS	1.00	1694.92	1,694.92
A	A. Sub total				1,02,331.27
B	B. Stock, Storage & Insurance @ 3% of A				3,069.94
C	Sub Total (C=A+B)				1,05,401.20
D	T&P @ 2% of C				2,108.02
E	Contingency @ 3% of C				3,162.04
F	Transportation @ 7.5% of C				7,905.09
G	Erection Charges @ 20% on PSC poles				
H	Erection Charges of DTR and Joist Poles @ 5%				1,405.99
I	Erection Charges @ 10%				7,728.14
J	Total				1,27,710.48
26	Material for earthing including masanory work for earth pit, salt, charcoal (K)	No	3	3784.73	11,354.19
27	Concreting of support C.C.,1;1;5;3, 0.375 Cum @ 6648.85/- (L) for WPB Pole.	No	4	2991.98	11,967.93
28	Couping with C.C. 1;1:5:3, 1125Cum @ Rs 6648.85 (M),	No	1	748.00	748.00
	S. Total				1,51,780.60
II	LT LINE 4x95+1x95x16mm2 XLPE AB cable =0.25 KM				
1	9 Mtr Long 300 Kg PSC Pole	No	1.00	3630.00	3,630.00
2	Base plate for support 20 Kg	No	1.00	361.34	361.34
3	8 Mtr Long 200 Kg PSC Pole (for stud)	Kg	4.00	2390.00	9,560.00
4	AB Cable(4x95+1x95+1x16) sq.mm.	Mtr	26.25	422.00	11,077.50
5	Suspension clamp with eye Hook for ABC	pair	1.00	193.00	193.00
6	Eye Hook for (XLPE AB Cable)	Pair	1.00	75.00	75.00
7	Pole clamp for eye Hook for (XLPE Cable)	No	1.00	240.00	240.00
8	Conductor Dead End Clamp Suitable for bare messenger XLPE AB cable (25-70 sq.mm.)	No	4.00	217.00	868.00
9	LT stay Set	Set	1	736.00	736.00
10	LT Stay insulator	No	1	19.00	19.00
11	LT Stay Clamp	Pair	5	350.00	1,750.00
12	7/12 SWG Stay Wire	Kg	8	79.00	632.00
13	GI Nut, Bolt & washer	Kg	2	74.00	148.00
14	Earthing coil	No	1	164.00	164.00
15	GI barbed wire/Anticlimbing device	Kg	3	74.00	222.00

16	Back clamp for Anticlimbing Device 25x3 mm, flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 4 Nos=(4x0.59x0.510)	Kg	0.60	78.00	46.80
17	Danger Plate	No	1.00	180.00	180.00
18	Back clamp for Danger Plate 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 1 Nos = (1x0.59x0.510)	Kg	0.60	78.00	46.80
19	Sundries	LS	1.00	423.73	423.73
A	A. Sub total				30,373.17
B	B. Stock, Storage & Insurance @ 3% of A				911.20
C	Sub Total (C=A+B)				31,284.36
D	T&P @ 2% of C				625.69
E	Contingency @ 3% of C				938.53
F	Transportation @ 7.5% of C				2,346.33
G	Erection Charges @ 20% on PSC poles				2,717.14
H	Erection Charges of DTR and Joist Poles @ 5%				
I	Erection Charges @ 10%				1,769.87
J	Total				39,681.91
20	Cement concreteing for stud/stay anchor plate with C.C. 1:2:4, 0.2 Cum @ 6500.00 (I)	No	1	1300.00	1,300.00
21	Couping with C.C. 1;1:5:3, 1125Cum @ Rs 6648.85 (J),	No	1	748.00	748.00
22	Concreting of support C.C. 1;1;5:3, 0.375 Cum @ 6648.85/- (K)	No	1	2493.32	2,493.32
	S. Total Rs				44,223.24
III	INSTALLATION OF 63 KVA S/S.				
1	WPB GI Pole160X152(11 Mtr. Long ,30.44 Kg/Mtr.)	No	2.00	27300.82	54,601.64
2	Pressure Channel (100x50x6) mm 2.8mtr . Long 2nos (9.56 Kg/Mtr) with Galvanizing	Kg	51.52	78.00	4,018.56
3	AB Swich & HG Fuse mounting Channel 75x40x6mm, 2.8mtr long 4Nos with Galvanisation charges	kg	76.16	78.00	5,940.48
4	Cantilever channel for supporting HG fuse 75x40x6 mm., MS Angle 1mtr long 2Nos (6.8kg/mtr) with Galvanisation charges.	Kg	13.6	78.00	1,060.80
5	Cantilever channel for supporting HG fuse 500x50x6 mm., MS Angle 1mtr long 2Nos (4.5kg/mtr) with Galvanisation charges.	Kg	9	69.00	621.00
6	Angle for cantilever arrangement for AB switch and HG fuse 50x50x6 mm 2mtr long each , 2Nos long each, 2Nos (4.5kg/mtr) with Galvanisation charges.	Kg	18	69.00	1,242.00
7	Angle for mounting LT distribution box (50x50x6) mm (4.5Kg/Mtr) with Galvanizing.	Kg	13.5	69.00	931.50
8	H/W fitting 70KN , 3Bolt	Pair	3	412.00	1,236.00

9	11 KV 5KN Polymer pin insulator	No	3	140.00	420.00
10	11 KV AB switch (200 Amp, 3 pole, 50 HZ)	Set	1	9080.00	9,080.00
11	11 KV HG Fuse (200 Amp, 3 pole) with PI	Set	1	6037.00	6,037.00
12	11 KV LA (9 KV,10 KA,) Station Class	No	3	1960.00	5,880.00
13	LT Distribution Box for 63 KVA S/S	No	1	26990.00	26,990.00
14	HT Stay Set (Complete)	Set	2	1434.00	2,868.00
15	Stay Insulator	No.	2	87.00	174.00
16	Stay Clamp	Kg	2	260.00	520.00
17	7/10 SWG Stay Wire	KG	20	77.00	1,540.00
18	55sq.mm. AAA conductor for jumpering	Km	0.05	43360.00	2,168.00
19	Wedge Connector for 55mm2 AAAC	No	6	100.00	600.00
20	40mm nominal bore GI pipe (medium gauge) earthing device with 3 mtr long.	No	7	1300.00	9,100.00
21	Earthing Coil	No	2	164.00	328.00
22	25x6 mm GI flat	Kg	84	72.00	6,048.00
23	GI Bolts, Nuts & washers	Kg	25	74.00	1,850.00
24	63KVA, 11/0.4 KV (AL) Transformer BIS Energy Level-II.	No	1	141309.00	1,41,309.00
25	1.1KV AL 1Cx95, 50 sq.mm. XLPE (Unmoured)	Mtr	40	103.00	4,120.00
26	Base plate	No	2	361.34	722.68
27	GI barbed wire/Anticlimbing device	Kg	6	74.00	444.00
28	Back clamp for Anticlimbing Device 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 4 Nos =(4x0.59x0.510)	Kg	4.81	78.00	375.53
29	Danger Plate	No	2	180.00	360.00
30	Back clamp for Danger Plate 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length	Kg	1.20	78.00	93.60
31	Sundries	Ls	1.00	1694.92	1,694.92
A	A. Sub total				2,92,374.70
B	B. Stock, Storage & Insurance @ 3% of A				8,771.24
C	Sub Total (C=A+B)				3,01,145.94
D	T&P @ 2% of C				6,022.92
E	Contingency @ 3% of C				9,034.38
F	Transportation @ 7.5% of C				22,585.95
G	Erection Charges @ 20% on PSC poles				
H	Erection Charges of DTR and Joist Poles @ 5%				10,089.40
I	Erection Charges @ 10%				9,935.80
J	Total				3,58,814.38
32	Material for masonry work for earth including masonry work for earth, pit, salt, charcoal etc	Ls	7	3784.73	26,493.10
33	Concreting of support C.C.,1;1;5;3, 0.37 Cum @ 6648.85/- for WPB Pole(11 Mtr WPB pole)	No	2	2991.98	5,983.97

34	Couping with C.C. 1;1:5:3, 1125Cum @ Rs 6648.85 .	No	2	748.00	1,496.00
35	Cement concreteing for stay anchor plate with C.C. 1:2:4, 0.2 Cum @ 6500.00 .	No	2	1300.00	2,600.00
36	Construction of plinth for new plinth mounted DSS .	No	1	28000.00	28,000.00
37	Construction of Brick Boundary wall & grill gate with Civil & MS Metal & sand Spreding and metal spreading to the new Plinth mounted DSS .	Rm	12	7300.12	87,601.42
	Total Rs.				5,10,988.87
	TOTAL RS.(PART-A, FOR 6-F TYPE QTRS.)				7,06,992.71
	PART-B				
I	Construction of 3P 3W Line with 3Cx50mm2 XLPE Cable - 0.020 Km				
1	Pole WPB GI 160x152 11 Mtr	No	1.00	27300.82	27,300.82
2	11KV V cross arm (10.5Kg each)	No	1.00	851.00	851.00
3	GI Back Clamp for V cross Arm (0.8kg each)	No	1.00	140.00	140.00
4	11 KV F clamp (GI)	No	1.00	135.00	135.00
5	11 KV 5KN Polymer pin insulator	No	3	140.00	420.00
6	12KV 10KA 11KV Lighting Arrestor Station Cl-II.	No	3.00	1960.00	5,880.00
7	(75x40x6) Mm GI Channel, 1.2 Mtr Long, 02 Nos for road support of Las.	Kg	16.32	78.00	1,272.96
8	Heat shrinkable joning kit suitable for 3Cx50 mm2 11KV XLPE Cable (outdoor Type)	No	4.00	1610.18	6,440.71
9	11KV AL 3Cx50 Sq.mm XLPE Round Armoured.	Mtr	21.00	859.00	18,039.00
10	7/12 SWG GI Stay Wire,	Kg	6.43	79.00	507.65
11	11 KV XLPE cable clamp to hold support wire.	No	21.00	22.77	478.19
12	Pole Clamp for Eye hook for XLPE cable.	Pair	4.00	240.00	960.00
13	Eye hook for XLPE cable	No	4.00	75.00	300.00
14	Suspension Clamp for XLPE cable	Pair	4.00	140.00	560.00
15	Conductor dead end clamp suitable for bare messenger XLPE Areial bunched cable (25-70 mm)	No	2.00	217.00	434.00
16	GI Flat 25 x6 mm for earthing	Kg	24.00	72.00	1,728.00
17	GI Pipe earthing 40 mm dia medium gauge (3.25mm thickness) 3 mtr long	No	3.00	1300.00	3,900.00
18	Earthing coil	No	1.00	164.00	164.00
19	GI Nut , Bolt & Washer of different sizes	Kg	5.00	74.00	370.00
20	100x50x6mm, MS Channel for straight cross arm (1.2mx16 pcs) (9.2kg/mtr)+(0.2mx0 pcs) 99.2kg/mtr) for tapping & cut point pole.	Kg	22.08	78.00	1,722.24
21	Anticlimbing Device (GI barbed with 3kg per support)	Kg	3.00	74.00	222.00
22	Back clamp for Anticlimbing Device 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 4 Nos=(8x0.59x0.510)	Kg	0.60	78.00	46.80
23	Danger Plate	No	1.00	180.00	180.00

24	Back clamp for Danger Plate 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 1 Nos=(2x0.59x0.510)	Kg	0.60	78.00	46.80
25	Sundries	LS	1.00	1694.92	1,694.92
A	A. Sub total				73,794.10
B	B. Stock, Storage & Insurance @ 3% of A				2,213.82
C	Sub Total (C=A+B)				76,007.92
D	T&P @ 2% of C				1,520.16
E	Contingency @ 3% of C				2,280.24
F	Transportation @ 7.5% of C				5,700.59
G	Erection Charges @ 20% on PSC poles				
H	Erection Charges of DTR and Joist Poles @ 5%				1,405.99
I	Erection Charges @ 10%				4,788.81
J	Total				91,703.71
26	Material for earthing including masanory work for earth pit, salt, charcoal .	No	3	3784.73	11,354.19
27	Concreting of support C.C.,1;1;5;3, 0.375 Cum @ 6648.85/- for WPB Pole.	No	4	2991.98	11,967.93
28	Couping with C.C. 1;1:5:3, 1125Cum @ Rs 6648.85 .	No	1	748.00	748.00
	S. Total				1,15,773.83
II	LT LINE 4x95+1x95x16mm2 XLPE AB cable =0.70 KM				
1	9 Mtr Long 300 Kg PSC Pole	No	3.00	3630.00	10,890.00
2	Base plate for support 20 Kg	No	3.00	361.34	1,084.02
3	8 Mtr Long 200 Kg PSC Pole (for stud)	Kg	4.00	2390.00	9,560.00
4	AB Cable(4x95+1x95+1x16) sq.mm.	Mtr	73.50	422.00	31,017.00
5	Suspension clamp with eye Hook for ABC	pair	3.00	193.00	579.00
6	Eye Hook for (XLPE AB Cable)	Pair	3.00	75.00	225.00
7	Pole clamp for eye Hook for (XLPE Cable)	No	3.00	240.00	720.00
8	Conductor Dead End Clamp Suitable for bare messenger XLPE AB cable (25-70 sq.mm.)	No	4.00	217.00	868.00
9	LT stay Set	Set	1	736.00	736.00
10	LT Stay insulator	No	1	19.00	19.00
11	LT Stay Clamp	Pair	5	350.00	1,750.00
12	7/12 SWG Stay Wire	Kg	8	79.00	632.00
13	GI Nut, Bolt & washer	Kg	6	74.00	444.00
14	Earthing coil	No	3	164.00	492.00
15	GI barbed wire/Anticlimbing device	Kg	9.00	74.00	666.00
16	Back clamp for Anticlimbing Device 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 4 Nos =(4x0.59x0.510)	Kg	1.81	78.00	141.18
17	Danger Plate	No	3.00	180.00	540.00

18	Back clamp for Danger Plate 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 1 Nos=(1x0.59x0.510)	Kg	1.81	78.00	141.18
19	Sundries	LS	1.00	423.73	423.73
A	A. Sub total				60,928.11
B	B. Stock, Storage & Insurance @ 3% of A				1,827.84
C	Sub Total (C=A+B)				62,755.95
D	T&P @ 2% of C				1,255.12
E	Contingency @ 3% of C				1,882.68
F	Transportation @ 7.5% of C				4,706.70
G	Erection Charges @ 20% on PSC poles				4,212.70
H	Erection Charges of DTR and Joist Poles @ 5%				
I	Erection Charges @ 10%				4,169.24
J	Total				78,982.39
20	Cement concreteing for stud/stay anchor plate with C.C. 1:2:4, 0.2 Cum @ 6500.00	No	1	1300.00	1,300.00
21	Couping with C.C. 1;1:5:3, 1125Cum @ Rs 6648.85	No	3	748.00	2,244.00
22	Concreting of support C.C. 1;1;5:3, 0.375 Cum @ 6648.85/-	No	3	2493.32	7,479.97
	S. Total Rs				90,006.35
III	INSTALLATION OF 63 KVA S/S.				
1	WPB GI Pole160X152(11 Mtr. Long ,30.44 Kg/Mtr.)	No	2.00	27300.82	54,601.64
2	Pressure Channel (100x50x6) mm 2.8mtr . Long 2nos (9.56 Kg/Mtr) with Galvanizing	Kg	51.52	78.00	4,018.56
3	AB Swich & HG Fuse mounting Channel 75x40x6mm, 2.8mtr long 4Nos with Galvanisation charges	kg	76.16	78.00	5,940.48
4	Cantilever channel for supporting HG fuse 75x40x6 mm., MS Angle 1mtr long 2Nos (6.8kg/mtr) with Galvanisation charges.	Kg	13.6	78.00	1,060.80
5	Cantilever channel for supporting HG fuse 500x50x6 mm., MS Angle 1mtr long 2Nos (4.5kg/mtr) with Galvanisation charges.	Kg	9	69.00	621.00
6	Angle for cantilever arrangement for AB switch and HG fuse 50x50x6 mm 2mtr long each , 2Nos long each, 2Nos (4.5kg/mtr) with Galvanisation charges.	Kg	18	69.00	1,242.00
7	Angle for mounting LT distribution box (50x50x6) mm (4.5Kg/Mtr) with Galvanizing.	Kg	13.5	69.00	931.50
8	H/W fitting 70KN , 3Bolt	Pair	3	412.00	1,236.00
9	11 KV 5KN Polymer pin insulator	No	3	140.00	420.00
10	11 KV AB switch (200 Amp, 3 pole, 50 HZ)	Set	1	9080.00	9,080.00
11	11 KV HG Fuse (200 Amp, 3 pole) with PI	Set	1	6037.00	6,037.00
12	11 KV LA (9 KV,10 KA,) Station Class	No	3	1960.00	5,880.00

13	LT Distribution Box for 100 KVA S/S	No	1	31086.00	31,086.00
14	HT Stay Set (Complete)	Set	2	1434.00	2,868.00
15	Stay Insulator	No.	2	87.00	174.00
16	Stay Clamp	Kg	2	260.00	520.00
17	7/10 SWG Stay Wire	KG	20	77.00	1,540.00
18	55sq.mm. AAA conductor for jumpering	Km	0.05	43360.00	2,168.00
19	Wedge Connector for 55mm ² AAAC	No	6	100.00	600.00
20	40mm nominal bore GI pipe (medium gauge) earthing device with 3 mtr long.	No	7	1300.00	9,100.00
21	Earthing Coil	No	2	164.00	328.00
22	25x6 mm GI flat	Kg	84	72.00	6,048.00
23	GI Bolts, Nuts & washers	Kg	25	74.00	1,850.00
24	100 KVA, 11/0.4 KV (AL) Transformer BIS Energy Level-II.	No	1	189025.00	1,89,025.00
25	1.1KV AL 1Cx95, 50 sq.mm. XLPE (Unmoured)	Mtr	40	103.00	4,120.00
26	Base plate	No	2	361.34	722.68
27	GI barbed wire/Anticlimbing device	Kg	6	74.00	444.00
28	Back clamp for Anticlimbing Device 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length 4 Nos=(4x0.59x0.510)	Kg	4.81	78.00	375.53
29	Danger Plate	No	2	180.00	360.00
30	Back clamp for Danger Plate 25x3 mm ,flat, 0.59 Kg/Mtr., flat of 0.510 Mtr. Length	Kg	1.20	78.00	93.60
31	Sundries	Ls	1.00	1694.92	1,694.92
A	A. Sub total				3,44,186.70
B	B. Stock, Storage & Insurance @ 3% of A				10,325.60
C	Sub Total (C=A+B)				3,54,512.30
D	T&P @ 2% of C				7,090.25
E	Contingency @ 3% of C				10,635.37
F	Transportation @ 7.5% of C				26,588.42
G	Erection Charges @ 20% on PSC poles				
H	Erection Charges of DTR and Joist Poles @ 5%				12,546.77
I	Erection Charges @ 10%				10,357.69
J	Total				4,21,730.80
32	Material for masonry work for earth including masonry work for earth, pit, salt, charcoal etc	Ls	7	3784.73	26,493.10
33	Concreting of support C.C.,1;1;5;3, 0.37 Cum @ 6648.85/- (L) for WPB Pole(11 Mtr WPB pole)	No	2	2991.98	5,983.97
34	Couping with C.C. 1;1;5;3, 1125Cum @ Rs 6648.85 (M),	No	2	748.00	1,496.00

35	Cement concreteing for stay anchor plate with C.C. 1:2:4, 0.2 Cum @ 6500.00 (N)	No	2	1300.00	2,600.00
36	Construction of plinth for new plinth mounted DSS (O)	No	1	28000.00	28,000.00
37	Construction of Brick Boundary wall & grill gate with Civil & MS Metal & sand Spreding and metal spreading to the new Plinth mounted DSS (M)	Rm	12	7300.12	87,601.42
	Total Rs.				5,73,905.29
	TOTAL RS.(PART-B, FOR 12-E TYPE QTRS.)				7,79,685.47
	Sub Total Rs.(PART-A+PART-B)				14,86,678.19
	Cess @1%				14,866.78
	Total Estimated Cost				15,01,544.97
	Total Estimated Cost in Figures				15,01,545.00
EXCESS	☐ LESS ☐ (Please Tick)	In Figure _____ % In word _____ %			
Quoted Amount in Figure					
Quoted Amount in word					

N:B- The Estimated cost is exclusive of GST .

Signature of Tenderer with seal

Sd/-
Asst. Project Manager (Elect)

Sd/-
Dy. Manager (Elect)

Sd/-
Project Manager (Elect)